

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

STATE: Rhode Island	
COUNTY: Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

1. NAME

COMMON:  
Moshassuck Square

AND/OR HISTORIC:  
American Screw Company Factories

2. LOCATION

STREET AND NUMBER:  
Stevens Street

CITY OR TOWN:  
Providence

STATE: Rhode Island, 02904      CODE: 38      COUNTY: Providence      CODE: 007

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
District <input checked="" type="checkbox"/> Building <input type="checkbox"/> Site <input type="checkbox"/> Structure <input type="checkbox"/> Object <input type="checkbox"/>	Public <input checked="" type="checkbox"/> Public Acquisition: Private <input type="checkbox"/> In Process <input type="checkbox"/> Both <input type="checkbox"/> Being Considered <input type="checkbox"/>	Occupied <input type="checkbox"/> Unoccupied <input checked="" type="checkbox"/> Preservation work in progress <input type="checkbox"/>	Yes: Restricted <input checked="" type="checkbox"/> Unrestricted <input type="checkbox"/> No: <input type="checkbox"/>
PRESENT USE (Check One or More as Appropriate)			
Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment <input type="checkbox"/>	Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum <input type="checkbox"/>	Park <input type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific <input type="checkbox"/>	Transportation <input type="checkbox"/> Other (Specify) <input checked="" type="checkbox"/> Formerly industrial and commercial; now unused Comments <input type="checkbox"/>

4. OWNER OF PROPERTY

OWNERS NAME:  
City of Providence

STREET AND NUMBER:  
Dorrance and Washington Streets

CITY OR TOWN: Providence      STATE: Rhode Island      CODE: 38

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:  
City Hall

STREET AND NUMBER:  
Dorrance and Washington Streets

CITY OR TOWN: Providence      STATE: Rhode Island      CODE: 38

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: .79 acre

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:  
Not so represented yet.

DATE OF SURVEY: Federal  State  County  Local

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN:      STATE:      CODE:

SEE INSTRUCTIONS

STATE:  
COUNTY:

FOR NPS USE ONLY  
ENTRY NUMBER  
DATE

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

Pre-Columbian       16th Century       18th Century       20th Century   
 15th Century       17th Century       19th Century

SPECIFIC DATE(S) (If Applicable and Known)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

Aboriginal	<input type="checkbox"/>	Education	<input type="checkbox"/>	Political	<input type="checkbox"/>	Urban Planning	<input checked="" type="checkbox"/>
Prehistoric	<input type="checkbox"/>	Engineering	<input type="checkbox"/>	Religion/Philosophy	<input type="checkbox"/>	Other (Specify)	<input type="checkbox"/>
Historic	<input type="checkbox"/>	Industry	<input checked="" type="checkbox"/>	Science	<input type="checkbox"/>	_____	
Agriculture	<input type="checkbox"/>	Invention	<input type="checkbox"/>	Sculpture	<input type="checkbox"/>	_____	
Art	<input checked="" type="checkbox"/>	Landscape	<input type="checkbox"/>	Social/Humanitarian	<input type="checkbox"/>	_____	
Commerce	<input type="checkbox"/>	Architecture	<input type="checkbox"/>	Theater	<input type="checkbox"/>	_____	
Communications	<input type="checkbox"/>	Literature	<input type="checkbox"/>	Transportation	<input type="checkbox"/>	_____	
Conservation	<input type="checkbox"/>	Military	<input type="checkbox"/>			_____	
		Music	<input type="checkbox"/>			_____	

STATEMENT OF SIGNIFICANCE (Include Personages, Dates, Events, Etc.)

These buildings are an intact grouping of XIX Century industrial architecture--functional, economical, interesting and vigorously handsome. They form a monument to Providence's and Rhode Island's early industrial inventiveness and development (the American Screw Company having been outstanding in inventiveness and success), so important in the history, prosperity and prominence of both city and state. Additionally, by their size and siting, they are an anchor or centre to an area of the city which badly needs a tangible, visible focal point more than it does the characterless expanses resulting from over-eager demolition and uninspired rebuilding.

This group of factory buildings, with its streets, alleys, open areas and pockets, sloping up from a still-flowing segment of the walled Blackstone Canal, has become a familiar landmark to local persons and to those driving in from the north-west--a landmark which would be much missed if destroyed. It has a certain rugged picturesque quality, certain visual delights and surprises not unlike those of an Italian hill village--rather unexpected but evident.

Many other larger or smaller factory groups--an important phase of American architectural performance from the very beginning of the XIX Century--have not survived or else have been swallowed within vast and uninteresting XX Century structures. The Moshassuck Square buildings stand, still, together as a once begun and finally completed group telling an industrial, civic and architectural story precisely placed within the period 1840-1873, unrevised, unenlarged.

The past significance of these buildings is in their history and original use. Their present significance lies in their architectural and landmark qualities. Their future significance will be in their continued existence and re-use.

(See Continuation Sheet)

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet -2)

STATE	
Rhode Island	
COUNTY	
Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

8. Significance.

Plans have been put forward for their preservation, internal conversion and use. These buildings, as they stand, are suitable to a variety of present-day purposes. They could house offices, studios, perhaps some retail shops and--not least--commodious and desirable dwelling units (cf. Boston's converted Atlantic Avenue wharf warehouses). Walkways for convenience and open areas for relaxation already exist; sufficient space for automobile parking already exists in adjacent, already-levelled areas.

It is much to be hoped that, when redevelopment of the Randall Square district is put in work, the Moshassuck Square--American Screw Company grouping will be retained as a very useful part and extraordinarily enhancing centre of the new community.

Plans to restore the Blackstone Canal from this section of Randall Square to its source near Market Square will also affect the restoration of the mill buildings. Restoration of a section of the Blackstone Canal in Lincoln is now under way.

7. DESCRIPTION

CONDITION	(Check One)					
	Excellent <input type="checkbox"/>	Good <input checked="" type="checkbox"/>	Fair <input type="checkbox"/>	Deteriorated <input type="checkbox"/>	Ruins <input type="checkbox"/>	Unexposed <input type="checkbox"/>
INTEGRITY	(Check One)			(Check One)		
	Altered <input checked="" type="checkbox"/>	Unaltered <input type="checkbox"/>		Moved <input type="checkbox"/>	Original Site <input checked="" type="checkbox"/>	

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

This is a complex of factory buildings of brick, timber and iron construction with stone and wood trim, dating mainly from c. 1840 to 1873. These factories were erected on land at the north end of Providence sloping upwards to the east from the Moshassuck River, which, at the time the earliest of them were built, formed a part of the Blackstone Canal system. The principal buildings are three or four storeys in height, mostly rectangular in form, with gable roofs and protruding stair towers, and generally with vast undivided loft space.

The first of these to be built was that of the Eagle Screw Company, a lengthy oblong with its long side fronting on Stevens Street. This is of three storeys topped by additional useable space under a full-length clerestorey or monitor astride the gable roof, giving the brick end-gables a stepped effect. The façades are pierced by numerous regularly-spaced windows having the simplest of stone sills and lintels. A sizeable square entrance- and stair-tower projects from the centre of the north front, and was originally surmounted by a wooden belfry or cupola of modest but dignified Greek Revival design. At the west or gable end is another stair tower of smaller dimensions, with recessed brick panels giving it minimal but noticeable adornment on its outer face. This tower has lost its original low wooden parapet or capping but retains its cornice. The original long building was given a gabled south wing of three storeys--making a T-shape--with an additional stair tower, but this was apparently not adequate for very long. (Much later this addition itself was extended and given a mansard roof.) To the south-east of the c. 1840 structure another similar factory was built, probably within ten years of the first one; but this does not have a clerestorey or a belfry. (Samuel M. Green writes, 1966, in his American Art that Thomas A. Tefft may have <sup>designed</sup> the Eagle Screw Company. 1840 is too early a date for Tefft. It is possible that he worked on this second factory, however.) These oldest buildings remain intact in their fabric and handsome in their functional simplicity and severe dignity.

Further factory space became needed after 1860, when the Eagle Screw Company merged with another firm to form the American Screw Company, and a second phase and style of building took place. A large triangular mill or factory was built higher up the slope, east of the c. 1840 building and north of the second factory. Enlargements were also made to the previously existing buildings. All this work is thought to be by a prominent mid-century Providence architect, Alpheus Morse, and could be dated c. 1865-1870. Morse was the designer of 30, Benefit Street (1869), the home of William G. Angell, president of the American Screw Company for many years. Detail on his house is like that of the mill buildings. The additions to the mills consist of two- and three-storey runs and corner blocks topped by decked mansard roofs, high and

(See Continuation Sheet)

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet)-1

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. Description.

angular in profile. These mansards cap still-severe brick walls with plain window openings; but there are at the eaves wooden architrave bands surmounted by projecting wooden cornices carried on curving brackets; there are bold capping cornices also at the break of the mansards; and all of the dormers are pedimented or gabled, with overhanging eaves, some being bracketted as well.

In 1873 expansion was again necessary, and the so-called Bay State Mill, believed also to be by Morse, was built on the north side of Stevens Street. This is a long gabled structure like its facing neighbour and is of four storeys and attic. There are the same numerous, regularly-spaced windows, though here with segmental brick arches instead of stone lintels. There is a projecting frontal stair tower as well. But at this point similarity ends, for in the 1873 building we have an "ornamental" factory and one which is meant to appear picturesque, however economically this is achieved. It is achieved through the use of certain features and details from the north Italian architectural vocabulary which Morse and others (notably Tefft) had previously used on public, church and domestic buildings locally--all of this adornment carried out in the manipulation of brickwork. The main portion of the factory and its tower have projecting cornices of brick courses supported on brick corbels or brackets closely spaced; the tower has a projecting brick "architrave" or wide belt at the eaves supported (visually, at least) by engaged brick posts on corbels; the sides of the tower are panelled, with brick fretwork at the tops of the panels. Round-headed windows are used in the tower, narrowed and paired in a Lombard Italianate manner at the fourth level. The tower, which is meant to soar above the main building like a campanile, has a very steep hipped roof originally topped by metal cresting, and eclectically displaying a metal bull's-eye dormer window of Louis XIII type in its front. At each end of the main building, in the gables, is a series of five round-headed windows, grouped, and growing smaller from centre to ends--another borrowing from Italy.

Two of the three tall, tapering, square smokestacks of this factory group still stand--simply and monumentally handsome--though few of the steel and wooden bridges once connecting various buildings across lanes and alleys remain. There are some other minor brick buildings or extensions which have not been individually described.

The basic condition of all these buildings is good. Recently vacated, they have been slightly damaged in the vacating process and moderately vandalised since. However, most damage appears limited to broken window glass or sashes and smashed doors. Their rugged masonry is in good order, and where there is wood trim it seems to have survived quite sturdily. The buildings mainly require a housecleaning and the restoration of ordinary continuous maintenance in order to serve or house any new use or uses to which they may be converted.

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet) -3

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

1. Name.

Common: Moshassuck Square--Additions to Original Nomination  
And/or Historic: Stillman White Brass Foundry; Fletcher Manufacturing  
Company Office; 127 Charles Street Commercial Block; Hewes  
Street Additions to the Bay State Mill

2. Location.

Street and Number: 1 Bark Street, 47 Charles Street, 127 Charles Street,  
Hewes Street  
City or Town: Providence  
State: Rhode Island, 02904 Code: 44 County: Providence Code: 007

3. Classification.

Category: District; Ownership: Public; Status: Unoccupied; Accessible  
to the Public: Yes--Restricted; Present Use: Formerly industrial  
and commercial; now unoccupied

4. Owner of Property: Same as on original nomination

5. Location of Legal Description: Same as on original nomination

6. Representation in Existing Surveys: Same as on original nomination

7. Description.

Condition: Fair; Integrity: Unaltered; Original Site

This group of brick industrial and commercial buildings is all that now remains of a once-large industrial district surrounding the Moshassuck Square--American Screw Company mills. Some of the American Screw Company structures were entered on the National Register in September, 1970, as part of a large urban renewal project comprising rehabilitation of the mill buildings along the Blackstone Canal as a center for a complex of new housing. All but two of the structures originally entered were destroyed by fire on July 5, 1971. Even now the surviving buildings comprise one of Providence's most visible links with its industrial past. In an effort to help maintain the character of the original innovative plan, adjacent surviving buildings are now to be rehabilitated.

Earliest of the buildings now being nominated is the mill office and warehouse of the Fletcher Manufacturing Company (Building 1 on the accompanying map). Located on a narrow trapezoidal lot between Charles Street and the Moshassuck River, it is the only surviving element of an extensive textile mill complex operated by this firm. The company, founded in 1793, moved to this area in the 1840's, incorporated in 1865 and, in 1869, erected a tall, mansarded, three-story brick office and warehouse. This

(See Continuation Sheet 4.)

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet)-4

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. Description.

severe, yet imposing, structure was clearly a "show-piece," surrounded as it was by the plain, squat mill buildings which up to then typified the Fletcher complex. Its crisp brickwork is relieved by regularly-spaced segmental-arched windows ornamented with brownstone and brick projected caps and sills. A handsome paneled brick frieze runs beneath the moulded wood cornice. The mansard is robustly ornamented with bracketed dormers, patterned slate-work and moulded deck capping. In the attic story of the Charles Street side is a freight door with hoist. The company flagstaff, that once-ubiquitous adjunct to any XIX-century factory complex, rises above a chimney on the narrow north façade. The mill office entrance, at 47 Charles Street, is set in a wood-paneled recess. Above it on a brownstone cartouche is proudly displayed the name of the firm in bold, projected lettering. A similar plaque on the north façade bears the date of construction--1869. A lower, more modest, three-story brick warehouse abuts the south end of the office. Visually and functionally, it complements the main building.

On the opposite embankment of the Moshassuck River from the Fletcher Manufacturing Company office stands the Stillman White Brass Foundry (Building 2). Separating, yet relating, the two is the Mill Street Bridge. Together, these formidable buildings suggest by their bulk and position a northern gateway into downtown Providence. Passing between them, one senses that he is leaving the outskirts and coming into the city itself.

The foundry occupies a constricted site bounded by Bark Street, the Moshassuck River and the Mill Street Bridge. Stillman White, who became a prominent Providence civic leader, began business here in 1856. The firm continued at this location through 1949. Construction and detail of the extant building, however, suggest that its three sections date in the late XIX and early XX centuries. (External evidence, e. g. the Providence atlases of 1875-1918, supports this assertion.) Though the roof profile varies from section to section, the coherent overall appearance of the building is due to its uniform brickwork, window openings and corbeled cornice. Lintels and sills are cast concrete throughout the building, save in some portions of the middle section where stone may be found. The two-story middle and south sections contained office, storage and work spaces. The north section was the foundry-room proper. It is identified by its tapering square chimney and four large wind-adjustable sheet-metal vents mounted on the roof. Though the interiors are badly damaged, they retain a series of overhead I-beam tracks used to transport castings to the Bark Street and Mill Street entrances. This straightforward working building is an effective contrast to the ornamented office across the bridge.

North of the bridge, at 127 Charles Street (Building 3) is a three-story brick commercial building. Erected c. 1900, it was designed to have stores on the ground floor and apartments above. Sandwiched between the Moshassuck River and Charles Street, it was originally flanked by numerous

(See Continuation Sheet 5.)

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet)-5

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. Description.

structures serving similar ends. Now it stands alone. The Charles Street facade presents two plate-glass store windows on either side of a narrow doorway. The second and third stories have regularly-spaced blind-segmental-arched windows. Finishing the flat roof-line of this modest building is a broad brick band decorated with corbeled string courses and capped with a moulded iron gutter. The side walls of the structure, not intended to be viewed from the street, have irregular fenestration and a stepped roof-line. A two-story wooden back porch projects from east side of the building at second- and third-floor levels. Supported on three massive diagonal braces, this wide porch has square posts with moulded caps and a characteristically simple balustrade with closely-spaced square balusters. The posts on the third-floor level support a sham arcade surmounted by a minimal entablature. This porch-loggia provided tenants of 127 Charles Street with a relatively pleasant open living space, overlooking the canal, markedly contrasting with their cramped indoor quarters.

Northeast of 127 Charles Street stands a large brick industrial building put up in two stages on a roughly triangular lot bounded by North Main Street, Hewes Street, and what was the upper end of Stevens Street. Erected as an addition to the Bay State Mill by the American Screw Company, the first section was completed c. 1882 (Building 6). This three-story brick block has a broad pitched roof and fine corbeled cornice. Its once-regular fenestration and wagon entrance on Stevens Street, illustrated in old wood-engraved views of the American Screw Company complex, are now masked or altered. Cable catwalks which formerly connected the 1882 building with the Bay State Mill have been demolished. Fine proportions and appropriate detailing make this building a worthy reminder of the area's industrial past.

An addition which appears on the insurance maps of 1918 (Building 7) runs north of the 1882 building on Hewes Street and curves around the original building and down its North Main Street side. Its later date is evidenced by the simpler cornice and near-flat roof. The northern end of this XX-century addition forms an impressive arc at the intersection of Hewes and North Main Streets. It is a landmark visible for some distance down North Main Street.

The condition of these buildings is varied: The Fletcher Manufacturing Company's mill office is occupied and in excellent condition. The additions to the Bay State Mill and 127 Charles Street are awaiting redevelopment and are unoccupied; though somewhat vandalized, their condition remains good. The Stillman White Brass Foundry, however, has been gutted by fire; the north wall and several window frames are missing.

(See Continuation Sheet 6.)



NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet)-6

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

8. Significance.

Because of restrictions imposed on the extent of the first Moshassuck Square nomination by an already-initiated urban renewal program, the buildings described on these Continuation Sheets 3-8 were not included at that time. Present renewal plans, however, make it possible to safeguard the remaining structures in the area, and they all merit preservation. These buildings, together with the shells of the burned-out American Screw Company mills, are the survivors of the formerly-vast Randall Square industrial district. They stand as a symbol of the diversity and vitality of Providence's industrial heritage.

Historically, the buildings provide an essential physical bond between the present and the origins of Providence's industrial prosperity. The first gristmill in the town of Providence was erected by John Smith in 1646, just north of the Stillman White Brass Foundry. East of the foundry site, Providence's first tannery was established in 1655. By the XIX century the Moshassuck River had become a part of the Blackstone Canal system, and numerous mills, factories and foundries had located in what became known as the Randall Square district. The commercial establishments along Charles Street served these firms and their employees. The Fletcher Manufacturing Company mill office, the Stillman White Brass Foundry, 127 Charles Street and the extant portions of the Bay State Mill complex all have a part in that history.

Rebuilding on cleared portions of the Randall Square area has already begun and makes the importance of retaining these surviving buildings as focal points in the proposed redevelopment fully evident. The sense of "presence" they lend to the area is remarkable--most tellingly in the visual relationship resulting from the position of the Fletcher office in relation to the White foundry. In their relationship to the Blackstone Canal, which it is hoped will be developed as a linear park amenity extending beyond the bounds of the Moshassuck Square project, the buildings now additionally proposed for nomination reinforce the visual and historical import of the area. Their inclusion in redevelopment plans for this area is, therefore, intended to add these just-mentioned visual and historical dimensions to the new complex.

9. Major Bibliographical References.

Hall, Joseph D., Jr., ed.: Biographical History of the Manufactures and Business Men of Rhode Island ... (Providence, Rhode Island, 1901), pp. 38, 54, 119.

The Providence Directory, and Rhode Island Business Directory, for the years 1856-1950.

The Providence House Directory, for the years 1895-1905.

(See Continuation Sheet 7.)

Cady, John Hutchins: The Civic and Architectural Development of Providence, 1636-1950 (Providence, 1957), p. 7, 171.

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet)-7

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

10. Geographical Data.

(Revised) Latitude and Longitude Coordinates Defining a Rectangle Locating the Property.

Corner	Latitude			Longitude		
	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds
NW	41	50	14.21	71	24	44.86
NE	41	50	12.34	71	24	35.02
SE	41	49	52.85	71	24	40.38
SW	41	49	51.34	71	24	50.26

Approximate Acreage of Nominated Property: 10

11. Form Prepared by

David Chase, Consultant  
Rhode Island Historical Preservation Commission,  
John Brown House, 52 Power Street  
Providence, Rhode Island, 02906

May 24, 1972

Code: 44 00

12. State Liaison Officer Certification: Same as on original nomination.\*\*

MOSHASSUCK SQUARE,  
Between Stevens and Hewes Streets  
to the north and Smith Street to  
the south; between North Main Street  
to the east and Charles Street to  
the west,  
Providence, Rhode Island.

INVENTORY OF BUILDINGS.  
(Revised as of May, 1972, to exclude  
structures destroyed since 1970 and  
to include four buildings now added  
to the original nomination to the  
National Register. Buildings are  
numbered below in accordance with the  
sketch-map of the revised district.)

*L Jue*

1. Fletcher Manufacturing Company Office, 47 Charles Street, 1869.  
Brick office and warehouse building of three stories carrying a  
mansard. (See description above.)

(See Continuation Sheet 8.)

\*\* see continuation sheet #8 for new certification

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet)-8

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Moshassuck Square. Inventory of Buildings.

2. Stillman White Brass Foundry, 1 Bark Street, 1856 ff. Gable-roofed brick structure with tall chimney. (See description above.)
3. 127 Charles Street Commercial Block, c. 1900. Simple brick store- and apartment-building of three stories with wooden porch-galleries across the back elevation. (See description above.)
4. Remaining portion of a southerly extension, of brick, of the second--1850's--factory of the Eagle Screw Company, which was gutted by fire in July, 1971, and subsequently razed. (See original nomination.)
5. Shell (roofless) of the original factory building, c. 1840, of the Eagle Screw Company. This was completely burned-out in the fire of July, 1971, but the brick carcass stands firmly, however, and will be re-used. (See original nomination.)
- 6.-7. Hewes Street Additions to the Bay State Mill (the latter now demolished: see original nomination), c. 1882 ff. Two-story range of brick annex buildings whose considered simplicity achieves distinction. (See description above.)

STATE LIAISON OFFICER CERTIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is: State.

Name \_\_\_\_\_

Title \_\_\_\_\_

Date \_\_\_\_\_

APPENDIX B.

AMENDED BOUNDARY OF THE MOSHASSUCK SQUARE HISTORIC DISTRICT

The boundary of the Moshassuck Square Historic District follows the center of Charles Street south from the intersection of Charles Street and Stevens Street to the intersection of Charles Street and Smith Street; then east along the center of Smith Street to North Main Street; then north along the center of North Main Street to Hewes Street; then southwest along the center of Hewes Street to Stevens Street; then west along the center of Stevens Street to Charles Street.

**9. MAJOR BIBLIOGRAPHICAL REFERENCES**

Green, Samuel M.: American Art. A Historical Survey (New York, 1966).  
 Greene, Welcome Arnold: The Providence Plantations for Two Hundred and Fifty Years (Providence, 1886), p. 264.  
 Cady, John Hutchins: The Civic and Architectural Development of Providence, 1636-1950. (Providence, 1957), p. 171.  
The Providence Journal, Vol. ? , No. ? , November 19, 1915, Section 5.

**10. GEOGRAPHICAL DATA**

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN ONE ACRE		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		41° 49' 48" N	71° 24' 42" W	
NE	° ' "	° ' "				
SE	° ' "	° ' "				
SW	° ' "	° ' "				

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE

**11. FORM PREPARED BY:**

NAME AND TITLE:  
 Richard B. Harrington, Consultant

ORGANIZATION: Rhode Island Historical Preservation Commission      DATE: June 18, 1970

STREET AND NUMBER:  
 State House, 90, Smith Street

CITY OR TOWN: Providence      STATE: Rhode Island, 02903      CODE: 38

**12. STATE LIAISON OFFICER CERTIFICATION      NATIONAL REGISTER VERIFICATION**

<p>As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:</p> <p>National <input type="checkbox"/>    State <input type="checkbox"/>    Local <input checked="" type="checkbox"/></p> <p>Name _____</p> <p>Title _____</p> <p>Date _____</p>	<p>I hereby certify that this property is included in the National Register.</p> <p>_____                  Chief, Office of Archeology and Historic Preservation</p> <p>Date _____</p> <p>ATTEST:</p> <p>_____                  Keeper of The National Register</p> <p>Date _____</p>
---	---

SEE INSTRUCTIONS



NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

Rhode Island

COUNTY

Providence

FOR NPS USE ONLY

ENTRY NUMBER

DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square

AND/OR HISTORIC: American Screw Company Factories

2. LOCATION

STREET AND NUMBER:

Stevens Street

CITY OR TOWN:

Providence

STATE:

Rhode Island

CODE

38

COUNTY:

Providence

CODE

007

3. PHOTO REFERENCE

PHOTO CREDIT: Avery Lord

DATE OF PHOTO: c. 1940-1950

NEGATIVE FILED AT: William Warner, 30, Benefit Street,  
Providence, Rhode Island, 02904

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

Air view of Providence, looking north, showing Moshassuck Square (circled) at upper right, the railroad running up the centre and the State House at left centre.



MONOSSUCC SQ. H.D.  
**CENTRAL PROVIDENCE**



NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY MAP FORM


(Type all entries - attach to or enclose with map)

STATE	Rhode Island
COUNTY	Providence
FOR NPS USE ONLY	
ENTRY NUMBER	

SEE INSTRUCTIONS

1. NAME		
COMMON: Moshassuck Square		
AND/OR HISTORIC: American Screw Company Factories		
2. LOCATION		
STREET AND NUMBER: Stevens Street		
CITY OR TOWN: Providence		
STATE: Rhode Island	CODE: 38	COUNTY: Providence
3. MAP REFERENCE		
SOURCE: Rhode Island Development Council: <u>Official Highway Map, 1969-70.</u>		
SCALE: 1 inch: 1/4 mile		
DATE: 1969		
4. REQUIREMENTS		
TO BE INCLUDED ON ALL MAPS		
1. Property boundaries where required.		
2. North arrow.		
3. Latitude and longitude reference.		

007



BARK STREET

EAGLE MILLS

BAY STATE MILL

STEVENS STREET

AMERICAN SCREW COMPANY

BLACKSTONE CANAL

CHARLES STREET

● INDICATES PHOTOGRAPHER STATION



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES


PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

<b>1. NAME</b>			
COMMON: Moshassuck Square			
AND/OR HISTORIC: American Screw Company Factories			
<b>2. LOCATION</b>			
STREET AND NUMBER: Stevens Street			
CITY OR TOWN: Providence			
STATE: Rhode Island	CODE 38	COUNTY: Providence	CODE 007
<b>3. PHOTO REFERENCE</b>			
PHOTO CREDIT: City of Providence: Dept. of Planning and Urban Development			
DATE OF PHOTO: 1970			
NEGATIVE FILED AT: City of Providence: Dept. of Planning and Urban Development, 10, Dorrance Street, Providence, Rhode Island			
<b>4. IDENTIFICATION</b>			
DESCRIBE VIEW, DIRECTION, ETC. Plan of the district, showing the important existing structures, the bounding streets and intervening lanes, surviving portion of Blackstone Canal at lower boundary.			



Van Slyck & Co. Boston.

EAGLE MILLS.

AMERICAN SCREW COMPANY.

PROVIDENCE, R. I.

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Moshassuck Square			
AND/OR HISTORIC: American Screw Company Factories			
2. LOCATION			
STREET AND NUMBER: Stevens Street			
CITY OR TOWN: Providence			
STATE: Rhode Island	CODE 38	COUNTY: Providence	CODE 007
3. PHOTO REFERENCE			
PHOTO CREDIT: Welcome Arnold Greene: <u>The Providence Plantations.</u>			
DATE OF <del>XXXX</del> lithograph: 1886			
NEGATIVE FILED AT: William Warner, 30, Benefit Street, Providence, Rhode Island, 02901			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC. Over-all view of the American Screw Company complex from the south- west, showing bridges between the buildings and showing the walled Blackstone Canal (still the same in 1970) in the foreground.			



KEEP PRODUCTS  
INC.  
*Vivacity*

FORMICA  
A FORMER ST.

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE

COUNTY

FOR NPS USE ONLY

ENTRY NUMBER

DATE

SEE INSTRUCTIONS

1. NAME **AMERICAN SCREW CO. (formerly Eagle Screw Co.)**

COMMON:

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER:

**Stevens Street**

CITY OR TOWN:

**Providence**

STATE:

**Rhode Island**

CODE

COUNTY:

**Providence**

CODE

3. PHOTO REFERENCE

PHOTO CREDIT: **Philip Seibert**

DATE OF PHOTO: **May, 1970**

NEGATIVE FILED AT: **30 Benefit Street  
Providence, Rhode Island**

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

**View looking west at the southernmost building of the  
American Screw Co., Eagle Mills. See key plan.**





NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square

AND/OR HISTORIC: American Screw Company Factories

2. LOCATION

STREET AND NUMBER:

Stevens Street

CITY OR TOWN:

Providence

STATE:

Rhode Island

CODE

38

COUNTY:

Providence

CODE

007

3. PHOTO REFERENCE

PHOTO CREDIT: Philip Seibert

DATE OF PHOTO: May, 1970

NEGATIVE FILED AT: William Warner, 30, Benefit Street,  
Providence, Rhode Island, 02904

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

View from south-west of mansard extensions (c. 1865-1870), showing bay which overlooks the Blackstone Canal.



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE  
Rhode Island

COUNTY  
Providence

FOR NPS USE ONLY

ENTRY NUMBER

DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square

AND/OR HISTORIC: American Screw Company Factories

2. LOCATION

STREET AND NUMBER:

Stevens Street

CITY OR TOWN:

Providence

STATE:

Rhode Island

CODE

38

COUNTY:

Providence

CODE

007

3. PHOTO REFERENCE

PHOTO CREDIT: Philip Seibert

DATE OF PHOTO: May, 1970

NEGATIVE FILED AT: William Warner, 30, Benefit Street,  
Providence, Rhode Island, 02901

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

Stair tower of the Bay State Mill--the three upper storeys seen  
from the south-west.



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square--Additions to Original Nomination

AND/OR HISTORIC: Fletcher Manufacturing Company Office (Building 1)

2. LOCATION

STREET AND NUMBER:

47 Charles Street

CITY OR TOWN:

Providence

STATE:

Rhode Island

CODE

44

COUNTY:

Providence

CODE

007

3. PHOTO REFERENCE

PHOTO CREDIT: B. Christopher Bene

DATE OF PHOTO: May, 1972

NEGATIVE FILED AT: Rhode Island Historical Preservation Commission  
John Brown House, 52 Power Street, Providence, Rhode Island, 02906

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

Fletcher Manufacturing Company's building seen from the east,  
showing the Rhode Island State House in the left background.



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE RHODE ISLAND	
COUNTY PROVIDENCE	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

<b>1. NAME</b>			
COMMON: Moshassuck Square--Additions to original nomination			
AND/OR HISTORIC: Fletcher Manufacturing Company Office			
<b>2. LOCATION</b>			
STREET AND NUMBER: 47 Charles Street			
CITY OR TOWN: Providence			
STATE: Rhode Island	CODE 44	COUNTY: Providence	CODE 007
<b>3. PHOTO REFERENCE</b>			
PHOTO CREDIT: Philip Seibert			
DATE OF PHOTO: May, 1970			
NEGATIVE FILED AT: William Warner, 30 Benefit Street, Providence, Rhode Island			
<b>4. IDENTIFICATION</b>			
DESCRIBE VIEW, DIRECTION, ETC. View toward the south along the east side of the Fletcher Manufacturing Company office, showing the Blackstone Canal.			



AMERICAN  
COLLECTION  
DEPARTMENT

TRESER BUILDING  
21 STEVENS ST.  
OLD PACKING CO.  
WELLS RYAN

America's  
*Smarter*  
SET

FORMICA

5



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Moshassuck Square			
AND/OR HISTORIC: American Screw Company Factories			
2. LOCATION			
STREET AND NUMBER: Stevens Street			
CITY OR TOWN: Providence			
STATE: Rhode Island	CODE 38	COUNTY: Providence	CODE 007
3. PHOTO REFERENCE			
PHOTO CREDIT: Philip Seibert			
DATE OF PHOTO: May, 1970			
NEGATIVE FILED AT: William Warner, 30, Benefit Street, Providence, Rhode Island, 02904			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC. View looking south from Stevens Street into Eagle Screw Company complex, showing (right) original c. 1840 factory and (left) c. 1865-1870 buildings; a remaining connector bridge is seen at the end of the alley.			



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

<b>1. NAME</b>			
COMMON: Moshassuck Square--Additions to Original Nomination			
AND/OR HISTORIC: 127 Charles Street Commercial Block (Building 3)			
<b>2. LOCATION</b>			
STREET AND NUMBER: 127 Charles Street			
CITY OR TOWN: Providence			
STATE: Rhode Island	CODE 44	COUNTY: Providence	CODE 007
<b>3. PHOTO REFERENCE</b>			
PHOTO CREDIT: B. Christopher Bene			
DATE OF PHOTO: May, 1972			
NEGATIVE FILED AT: Rhode Island Historical Preservation Commission John Brown House, 52 Power Street, Providence, Rhode Island, 02906			
<b>4. IDENTIFICATION</b>			
DESCRIBE VIEW, DIRECTION, ETC.  127 Charles Street seen from the northeast, showing rear galleries above the Blackstone Canal.			



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square--Additions to Original Nomination

AND/OR HISTORIC: Hewes Street Additions to the Bay State Mill (Building 6)

2. LOCATION

STREET AND NUMBER:  
Hewes Street

CITY OR TOWN:  
Providence

STATE:  
Rhode Island

CODE 44	COUNTY: Providence
------------	-----------------------

CODE 007
-------------

3. PHOTO REFERENCE

PHOTO CREDIT: B. Christopher Bene


DATE OF PHOTO: May, 1972

NEGATIVE FILED AT: Rhode Island Historical Preservation Commission,  
John Brown House, 52 Power Street, Providence, Rhode Island, 02906

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

View of the additions from the northeast, showing the rounded corner where Hewes Street meets North Main Street (running off to the left).



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS.

1. NAME

COMMON: Moshassuck Square--Additions to Original Nomination

AND/OR HISTORIC: Stillman White Brass Foundry (Building 2)

2. LOCATION

STREET AND NUMBER:

1 Bark Street

CITY OR TOWN:

Providence

STATE:

Rhode Island

CODE

44

COUNTY:

Providence

CODE

007

3. PHOTO REFERENCE

PHOTO CREDIT: B. Christopher Bene

DATE OF PHOTO: May, 1972

NEGATIVE FILED AT: Rhode Island Historical Preservation Commission  
John Brown House, 52 Power Street, Providence, Rhode Island, 02906

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

View of the brass foundry from the southeast.





NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Moshassuck Square			
AND/OR HISTORIC: American Screw Company Factories			
2. LOCATION			
STREET AND NUMBER: Stevens Street			
CITY OR TOWN: Providence			
STATE: Rhode Island	CODE 38	COUNTY: Providence	CODE 007
3. PHOTO REFERENCE			
PHOTO CREDIT: Philip Seibert			
DATE OF PHOTO: May, 1970			
NEGATIVE FILED AT: William Warner, 30, Benefit Street, Providence, Rhode Island, 02901			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC. The factory complex of the American Screw Company as existing to-day, photographed from the west.			



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE	
COUNTY	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME AMERICAN SCREW CO. (formerly Eagle Screw Co.)

COMMON:

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER:

Stevens Street

CITY OR TOWN:

Providence

STATE:

Rhode Island

CODE

COUNTY:

Providence

CODE

3. PHOTO REFERENCE

PHOTO CREDIT: Philip Seibert

DATE OF PHOTO: May, 1970

NEGATIVE FILED AT: 30 Benefit Street  
Providence, Rhode Island

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

View overlooking the south wall of the south wing of the main building of the Eagle Mill complex. It is connected by bridge to the triangular building, the corner of which shows in the foreground.



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE


NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM


(Type all entries - attach to or enclose with photograph)

STATE	
COUNTY	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME <b>AMERICAN SCREW CO. (formerly Eagle Screw Co.)</b>			
COMMON:			
AND/OR HISTORIC:			
2. LOCATION			
STREET AND NUMBER:			
Stevens Street			
CITY OR TOWN:			
Providence			
STATE:	CODE	COUNTY:	CODE
Rhode Island		Providence	
3. PHOTO REFERENCE			
PHOTO CREDIT: Philip Seibert			
DATE OF PHOTO: May, 1970			
NEGATIVE FILED AT: 30 Benefit Street Providence, Rhode Island			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC.			
View of the west side of the main building of the Eagle Mills; the south wall of the monitor-roofed mill, a section of the original south wing with mansard roof added, and a later addition with mansard roof (post 1965) on the right.			



 Buildings nominated



MOSHASSUCK SQUARE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY MAP FORM

(Type all entries - attach to or enclose with map)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square--Revised District

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER: Between Stevens and Hewes Streets to the north and Smith Street to the south; between North Main Street to the east and Charles Street to the west

CITY OR TOWN:  
Providence

STATE:  
Rhode Island

CODE  
44

COUNTY:  
Providence

CODE  
007

3. MAP REFERENCE

SOURCE:  
Eric Hertfelder, Rhode Island Historical Preservation Commission

SCALE: Sketch-map; none given

DATE: May, 1972

4. REQUIREMENTS

TO BE INCLUDED ON ALL MAPS

1. Property boundaries where required.
2. North arrow.
3. Latitude and longitude reference.

Note: This map shows the District's area as revised due to the subtraction of destroyed buildings and the addition of certain others to the original nomination.







UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE

Rhode Island

COUNTY

Providence

FOR NPS USE ONLY

ENTRY NUMBER

DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square

AND/OR HISTORIC: American Screw Company Factories

2. LOCATION

STREET AND NUMBER:

Stevens Street

CITY OR TOWN:

Providence

STATE:

Rhode Island

CODE

38

COUNTY:

Providence

CODE

007

3. PHOTO REFERENCE

PHOTO CREDIT: Philip Seibert


DATE OF PHOTO: May, 1970

NEGATIVE FILED AT: William Warner, 30, Benefit Street,  
Providence, Rhode Island, 02901

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

Partial view, looking north, of first Eagle Screw Company factory, showing monitor roof and west stair tower; the roof of the Bay State Mill tower is seen beyond.



**GEOGRAPHICAL COORDINATES**

	<u>Latitude</u>	<u>Longitude</u>
NE	41° 50' 12.34" N	71° 24' 35.02" W
SE	41° 49' 52.85" N	71° 24' 40.38" W
SW	41° 49' 51.34" N	71° 24' 50.26" W
NW	41° 50' 14.21" N	71° 24' 44.86" W

NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY MAP FORM

(Type all entries - attach to or enclose with map)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square--Revised District

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER: Between Stevens and Hewes Streets to the north and Smith  
Street to the south; between North Main Street to the east and Charles  
Street to the west

CITY OR TOWN:

Providence

STATE:

Rhode Island

CODE

14

COUNTY:

Providence

CODE

007

3. MAP REFERENCE

SOURCE:

U. S. Geological Survey

SCALE: 1: 24,000

DATE: 1957

4. REQUIREMENTS

TO BE INCLUDED ON ALL MAPS

1. Property boundaries where required.
2. North arrow.
3. Latitude and longitude reference.

Note: This map shows the District's area as revised due to the subtraction of destroyed buildings and the addition of certain others to the original nomination.



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE

Rhode Island

COUNTY

Providence

FOR NPS USE ONLY

ENTRY NUMBER

DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square

AND/OR HISTORIC: American Screw Company Factories

2. LOCATION

STREET AND NUMBER:

Stevens Street

CITY OR TOWN:

Providence

STATE:

Rhode Island

CODE

38

COUNTY:

Providence

CODE

007

3. PHOTO REFERENCE

PHOTO CREDIT: Rhode Island Historical Society


DATE OF PHOTO: Pre-1865

NEGATIVE FILED AT: William Warner, 30, Benefit Street,  
Providence, Rhode Island, 02904

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

View towards east, showing earliest factories (1840's) of the  
Eagle Screw Company with Blackstone Canal in centre foreground.



Removed  
for Prov  
Book  
25 Feb 06

AMERICAN SCREW CO. EAGLE MILLS, PROVIDENCE.

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM


(Type all entries - attach to or enclose with photograph)

STATE	
COUNTY	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

<b>1. NAME</b>			
COMMON: American Screw Co. (formerly Eagle Screw Co.)			
AND/OR HISTORIC:			
<b>2. LOCATION</b>			
STREET AND NUMBER:			
Stevens Street			
CITY OR TOWN:			
Providence			
STATE:	CODE	COUNTY:	CODE
Rhode Island		Providence	
<b>3. PHOTO REFERENCE</b>			
PHOTO CREDIT: R. I. Historical Society Scrapbook material			
DATE OF PHOTO:			
NEGATIVE FILED AT: 30 Benefit Street			
Providence, Rhode Island			
<b>4. IDENTIFICATION</b>			
DESCRIBE VIEW, DIRECTION, ETC.			
Old engraving done of the Eagle Mills from the same point of view as the one of the Bay State Mill.			





AMERICAN SCREW CO. BAY STATE MILL, PROVIDENCE.

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square

AND/OR HISTORIC: American Screw Company Factories

2. LOCATION

STREET AND NUMBER:  
Stevens Street

CITY OR TOWN:  
Providence

STATE:  
Rhode Island

CODE

38

COUNTY:

Providence

CODE

007

3. PHOTO REFERENCE

PHOTO CREDIT: Rhode Island Historical Society

DATE OF ~~XXXXX~~ wood-engraving: c. 1875-1885

NEGATIVE FILED AT: William Warner, 30, Benefit Street,  
Providence, Rhode Island, 02904

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

View of the Bay State Mill from the south-west. (For a clear view, the artist did not include the existing buildings of the former Eagle Screw Company in the foreground.)



PACKINGS  
INSULATIONS  
CORPORATION

A  
d  
m  
i  
r  
a  
l

TELEPHONE

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE  
Rhode Island

COUNTY  
Providence

FOR NPS USE ONLY

ENTRY NUMBER

DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Moshassuck Square

AND/OR HISTORIC: American Screw Company Factories

2. LOCATION

STREET AND NUMBER:  
Stevens Street

CITY OR TOWN:  
Providence

STATE:  
Rhode Island

CODE

38

COUNTY:

Providence

CODE

007

3. PHOTO REFERENCE

PHOTO CREDIT: Philip Seibert


DATE OF PHOTO: May, 1970

NEGATIVE FILED AT: William Warner, 30, Benefit Street,  
Providence, Rhode Island, 02904

4. IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC.

View towards the south-west taken from the north side of Stevens Street, showing (right half) the earliest factory--minus belfry, and (left) mid-XIX Century extensions.



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Rhode Island	
COUNTY Providence	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

<b>1. NAME</b>			
COMMON: Moshassuck Square-- Addition to original nomination			
AND/OR HISTORIC: Eagle Screw Company and 127 Charles Street Commercial Block			
<b>2. LOCATION</b>			
STREET AND NUMBER: Stevens Street (Eagle Screw Company) and 127 Charles Street			
CITY OR TOWN: Providence			
STATE: Rhode Island	CODE 44	COUNTY: Providence	CODE 007
<b>3. PHOTO REFERENCE</b>			
PHOTO CREDIT: Drawn by Karen Noel			
DATE OF PHOTO: Copy negative May, 1972			
NEGATIVE FILED AT: William Warner, 30 Benefit Street, Providence, Rhode Island			
<b>4. IDENTIFICATION</b>			
DESCRIBE VIEW, DIRECTION, ETC. Architect's drawing of proposed restoration of Eagle Screw Company Building and 127 Charles Street Commercial Block. View is to the south at the intersection of Stevens and Charles streets.			